

**PROPOSAL BID FORM****IMPROVEMENTS TO HENRY COUNTY AIRPORT  
HAMPTON, GEORGIA****TERMINAL BUILDING AND TERMINAL AREA IMPROVEMENTS**  
**BASE BID**

<b>SUMMARY OF QUANTITIES</b>							
Item No.	FAA Item No.	Misc/ GDOT Item No.	Description	Approx. Qty	Unit	Unit Price	Amount
1	105		Mobilization	1	LS		
2		163	Construct, Maintain and Remove Inlet Sediment Trap (Sd2-P: Pigs in a Blanket)	2	EA		
3		163	Construct, Maintain and Remove Inlet Sediment Trap (Sd2-F: Filter Ring)	3	EA		
4		171	Orange Construction Fence	105	LF		
5	P-101-5.1		Transitional Milling	1,780	SY		
6	P-151-4.1		Grubbing	1	AC		
7	P-156-5.1		Temporary Seeding Complete	1	AC		
8		210	Grading Complete	1	LS		
9		411	Portland Concrete Sidewalk, 4" thick in Xmm, for Sidewalk, Concrete Strip, Dumpster Pad, and Staging Area	590	SY		
10		438	Rollback Curb and Gutter, 24"	<b>1045</b>	LF		
11	P-209-5.1		Crushed Aggregate Base Course, including Bituminous Prime Coat, 8" Thick	2,875	SY		
12	P-603-5.1		Bituminous Tack Coat	288	GAL		
13		402	Recycled Asphaltic Concrete, 12.5mm, Superpave, 2" thick, GP 2 only, including Bituminous Materials and Hydrated Lime	1,680	TON		
14		402	Recycled Asphaltic Concrete, 19mm, Superpave, 2," thick, GP 1 or 2, including Bituminous Materials and Hydrated Lime	320	TON		
15		444	Sawcut, full depth	595	LF		
16	P-605-5.1		Crack Seal Apron Pavement	25,000	LF		
17	P-605-5.2		Crack Seal Parking Lot Pavement	25,000	LF		
18	P-620-5.1		Runway and Taxiway Marking, Type II (Yellow), including Reflective Material (Type III, Gradation A) and Microbicide	825	SF		
19	P-620-5.2		Parking Stall Marking, Type II (White), including Microbicide, 4" wide	400	SF		
20		636	ADA Accessible Parking Stall Signs, including posts and installation	2	EA		

21	F-162-5.1		Erect Chain Link Fence, 8' high, Black Vinyl Coated with 3 strands barbed wire	820	LF		
22	F-162-5.2		Erect Chain Link Fence, 8' high, Black Vinyl Coated with 3 strands barbed wire, Screened, surrounding dumpster area and mechanical equipment	95	LF		
23	F-162-5.3		Install 14' wide Motorized Sliding Gate, 6' high, Black Vinyl Coated Chain Link with 3 strands of barbed wire	1	EA		
24	F-162-5.4		Install 3' wide Man Gate, 8' high, Black Vinyl Coated Chain Link with 3 strands of barbed wire	2	EA		
25	F-162-5.5		Install 3' wide Man Gate, 8' high, Black Vinyl Coated Chain Link with 3 strands of barbed wire and keypad entry	1	EA		
26	D-751-5.1		Pre-Cast Reinforced Concrete Drop Inlet, 4' dia., including Frame and Grate	1	EA		
27	T-901-5.1		Permanent Seeding Complete	1	AC		
28	T-904-5.1		Sodding	355	SY		
29	T-908-5.1		Mulching	1	AC		
30	C-100-5.1		Wheel Stops	15	EA		
31	C-101-5.1		Aircraft Tie-Downs, per set	3	EA		
32	L-103-5.1		Refurbish Airport Beacon Tower	1	EA		
33			Refurbish Airport Viewing Tower, including Lead Abatement	1	EA		
34	L-109-5.1		Refurbish Airport Electrical Vault	1	EA		
35		610	Remove Existing FBO/Terminal Building, excluding asbestos abatement	1	LS		
36		610	Remove Existing Chain Link Fence, all sizes and types	750	LF		
37		610	Remove Existing Motorized Sliding Gate, including motor, bollards, electric pole, wiring and all appurtenances	1	LS		
38		610	Remove Existing Pavement, full depth	3,055	SY		
39		610	Remove 6" PVC Storm Pipe	18	LF		
40		610	Remove Existing Drop Inlet	1	EA		
41		610	Remove Underground Electrical Cable	1,333	LF		
42		610	Remove Underground Telephone Cable	257	LF		
43		610	Remove Existing Water Line and appurtenances	61	LF		
44		610	Remove Airport Signs and Poles	18	EA		
45		610	Remove Utility Pole	2	EA		
46			Install Underground Telephone Cable (AT&T)	282	LF		
47		682	Install Underground Electric Cable	286	LF		
48			Install Underground Telephone Cable	292	LF		
49			6" PVC Water Line	78	LF		

50			6" PVC Sanitary Sewer Line	71	LF		
51			Grease Trap, 1,500 Gallon	1	EA		
52	L-108-5.1		Trench and Backfill for Direct Buried Cable, 18 inch minimum depth	860	LF		
53		DIVISION 10	Construct New Terminal Building, Complete	1	LS		
54			Catering Kitchen Equipment Allowance @ \$25,000.00; excluding installation and/or delivery	1	LS		
55			Cash Allowance @ \$75,000.00	1	LS		
56			<b>Fire Hydrant Complete incl. Materials, Installation, Tap</b>	1	EA		

TOTAL:	
--------	--

Signature: \_\_\_\_\_  
(Bidder)

BY: \_\_\_\_\_  
NAME  
\_\_\_\_\_  
TITLE

Business Address: \_\_\_\_\_  
\_\_\_\_\_

Telephone Number \_\_\_\_\_

Manufacturer's or Contractor's I.D. No. \_\_\_\_\_