



**Henry County
Purchasing Department**
140 Henry Parkway, McDonough, GA 30253
Phone: 770-288-6027 Fax: 770-288-6047

Website: henrycounty-ga.com/purchasing

ADDENDUM #1
Issued 4/28/2021

Bid # 21-79
SR 20 at Turner Church Road
Due Date and Time: May 5, 2021, 3:00 PM

The following items take precedence over referenced portions of the documents for the above-named project and in executing a contract, will become a part thereof. Where any item in the documents is supplemented hereby, the original requirements will remain in effect. All supplemental conditions will be considered as added thereto. Where any original item is amended, voided or superseded hereby, the provisions of such items not so specifically amended, voided or superseded will remain in effect.

This form must be signed and attached to the bid to acknowledge receipt of this Addendum.
Failure to acknowledge any addenda will result in a non-responsive bid.

***Bid Price Sheet has been revised and replaced.**

Company's Name

Date

Authorized Representative's Name

Authorized Representative's Signature

Bid #21-79
SR 20 at Turner Church Road
Questions and Answers

- 1. Question:** The typical sections for this job shows Class 3 Concrete Paving. However, Bid Item #0050 is for Class 1 Paving. Please revise the Bid Item description to match the plans (Class 3 Concrete).
Answer: **Bid Item sheet has been revised to reflect Class 3 Concrete.**
- 2. Question:** Can the completion date of 300 calendar days please be extended to a minimum of 1.5 years to account for any utility relocations in order for the Prime Contractor to complete the construction according to the plans provided?
Answer: **300 calendar days shall remain in place for completion of the construction.**

Bid # 21-79
SR 20 at Turner Church Road
Bid Price Sheet- REVISED

LINE NO.	ITEM NO.	ITEM DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	EXTENDED PRICE
		ROADWAY				
0005	210-0100	GRADING COMPLETE - SP5325	LS	1		
0010	150-1000	TRAFFIC CONTROL - SP5325	LS	1		
0015	310-1101	GR AGGR BASE CRS, INCL MATL	TN	3,601		
0020	318-3000	AGGR SURF CRS	TN	250		
0025	402-1812	RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	TN	2,000		
0030	402-3130	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM MATL & H LIME	TN	1,500		
0035	402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	550		
0040	402-3121	RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	TN	1,100		
0045	413-0750	TACK COAT	GL	1,000		
0050	430-0200	PLAIN PC CONC PVMT, CL 3 CONC, 10 INCH THK	SY	262		
0055	432-5010	MILL ASPH CONC PVMT, VARIABLE DEPTH	SY	700		
0060	441-0016	DRIVEWAY CONCRETE, 6 IN TK	SY	35		
0065	441-4020	CONC VALLEY GUTTER, 6 IN	SY	50		
0070	441-0050	CONC SLOPE DRAIN	SY	31		

Company's Name: _____ Date: _____

0075	441-0108	CONC SIDEWALK, 8 IN	SY	400		
0080	441-0303	CONC SPILLWAY, TP 3	EA	5		
0085	441-0754	CONCRETE MEDIAN, 7 1/2 IN	SY	830		
0090	441-6222	CONC CURB & GUTTER, 8 IN X 30 IN, TP 2	LF	1,600		
0095	441-6745	CONC CURB & GUTTER, 8 IN X 32 IN, TP 9	LF	320		
0100	441-6720	CONC CURB & GUTTER, 6 IN X 30 IN, TP 7	LF	250		
0105	441-5025	CONCRETE HEADER CURB, 4 IN, TP 9	LF	80		
0110	446-1100	PVMT REINF FABRIC STRIPS, TP 2, 18 INCH WIDTH	LF	3,017		
0115	500-3200	CLASS B CONCRETE	CY	3		
0120	550-1180	STORM DRAIN PIPE, 18 IN, H 1-10	LF	360		
0125	550-2180	SIDE DRAIN PIPE, 18 IN, H 1-10	LF	100		
0130	550-4218	FLARED END SECTION 18 IN, STORM DRAIN	EA	7		
0135	550-3618	SAFETY END SECTION 18 IN, SIDE DRAIN, 6:1 SLOPE	EA	4		
0140	668-2100	DROP INLET, GP 1	EA	4		
0145	668-1100	CATCH BASIN, GP 1	EA	4		
0150	603-2181	STN DUMPED RIP RAP, TP 3, 18 IN	SY	68		
0155	603-7000	PLASTIC FILTER FABRIC	SY	68		
0160	643-8210	WOOD FENCE (3 SPLIT RAIL WITH WOVEN WIRE ATTACHED)	LF	800		
0165	643-0050	TEMPORARY FIELD FENCE	LF	1,600		
0170	643-0050	TEMPORARY FIELD FENCE - ELECTRIC	LF	700		
0175	643-0010	FIELD FENCE WOVEN WIRE	LF	1,600		

Company's Name: _____ Date: _____

0180	643-8405	SPECIAL DESIGN, ELECTRIC FIELD FENCE, 5 STRAND WITH FIBERGLASS LINE POSTS	LF	800		
		EROSION CONTROL				
0185	163-0301	CONSTRUCT AND REMOVE CONSTRUCTION EXITS	EA	4		
0190	165-0101	MAINTENANCE OF CONSTRUCTION EXIT	EA	4		
0195	171-0030	TEMPORARY SILT FENCE, TYPE C	LF	1,793		
0200	163-0240	MULCH	TN	26		
0205	163-0232	TEMPORARY GRASSING	AC	2		
0210	700-9300	SOD	SY	10,226		
0215	700-8100	FERTILIZER NITROGEN CONTENT	LB	200		
0220	700-8000	FERTILIZER MIXED GRADE	TN	2		
0225	163-0550	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	EA	11		
0230	163-0528	CONSTRUCT AND REMOVE FABRIC CHECK DAM - TYPE C SILT FENCE	LF	1,440		
0235	165-0030	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	LF	897		
0240	165-0041	MAINTENANCE OF CHECK DAMS - ALL TYPES	LF	720		
0245	165-0105	MAINTENANCE OF INLET SEDIMENT TRAP	EA	6		
0250	163-0503	CONSTRUCT AND REMOVE SILT CONTROL GATE, TP 3	EA	6		
0255	165-0087	MAINTENANCE OF SILT CONTROL GATE, TP 3	EA	3		
0260	167-1500	WATER QUALITY INSPECTIONS	MO	12		

Company's Name: _____ Date: _____

0265	167-1000	WATER QUALITY MONITORING AND SAMPLING	EA	12		
0270	700-7000	AGRICULTURAL LIME	TN	8		
		LIGHTING				
0275	681-0530	LIGHTING STD, STEEL, 30 FT MH	EA	14		
0280	681-6290	LUMINAIRE, TP 3, LED	EA	14		
0285	682-3485	MULT COND CABLE, TP RHW, 2-#8-1-#8	LF	2,115		
0290	682-1509	CABLE, TP RHH/RHW, AWG NO 2	LF	155		
0295	682-6120	CONDUIT, RIGID, 2 IN	LF	50		
0300	682-6219	CONDUIT, NONMETL, TP 2, 1 IN	LF	210		
0305	682-8500	ELECTRICAL POWER SERVICE ASSEMBLY (AERIAL SERVICE POINT)	EA	1		
0310	682-9021	ELECTRICAL JUNCTION BOX, CONC GROUND MOUNTED	EA	3		
0315	682-9950	DIRECTIONAL BORE - 3 IN	LF	350		
		LANDSCAPING				
0320	700-9300	SOD	SY	136		
0325	702-0212	CRATAEGUS VIRIDIS	EA	3		
0330	702-0470	ILEX VOMITORIA NANA - 5 GAL	EA	216		
0335	702-9005	SPRING APPLICATION FERTILIZER SIZE	LB	20		
0340	702-9025	LANDSCAPE MULCH (BLACK HARDWOOD MULCH)	SY	526		
0345	702-0228	CUPRESSOCYPARIS LEYLANDII	EA	42		
0350	725-0010	WEED CONTROL (3.5 OZ BOND FABRIC WEED BLOCK)	SY	526		

Company's Name: _____ Date: _____

		SIGNING & MARKING				
0355	429-1000	RUMBLE STRIPS	EA	3		
0360	636-1033	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 9	SF	66		
0365	636-1041	HIGHWAY SIGNS, TP 2 MATL, REFL SHEETING, TP 9	SF	335		
0370	636-1036	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 11	SF	158		
0375	636-2070	GALV STEEL POSTS, TP 7	LF	556		
0380	636-2080	GALV STEEL POSTS, TP 8	LF	410		
0385	636-2090	GALV STEEL POSTS, TP 9	LF	40		
0390	636-3010	GROUND-MOUNTED BREAKAWAY SIGN SUPPORT	EA	18		
0395	653-1502	THERMOPLASTIC SOLID TRAF STRIPE, 5 IN, YELLOW	LF	1,530		
0400	653-2602	THERMOPLASTIC SOLID TRAF STRIPE, 6 IN, YELLOW	LF	1,278		
0405	653-1906	THERMOPLASTIC SOLID TRAF STRIPE, 6 IN, WHITE	LF	2,591		
0410	653-1804	THERMOPLASTIC SOLID TRAF STRIPE, 8 IN, WHITE	LF	610		
0415	653-4830	THERMOPLASTIC SKIP TRAF STRIPE, 18 IN, WHITE	GLF	116		
0420	653-0296	THERMOPLASTIC PVMT MARKING, WORD, TP 15	EA	4		
0425	653-6006	THERMOPLASTIC TRAF STRIPING, YELLOW	SY	207		
0430	654-1001	RAISED PVMT MARKERS TP 1	EA	76		
0435	654-1003	RAISED PVMT MARKERS TP 3	EA	6		

Company's Name: _____ Date: _____

Total bid amount \$ _____
(numbers)

Total bid amount _____
(words)

Company's Name

Date

Authorized Representative's Name
(Print or Type)

Authorized Representative's Signature